INTERNATIONAL INDIAN SCHOOL - AL JUBAIL
Eastern Province - Kingdom of Saudi Arabia
Licenced By Ministry of Education K.S.A. Vide Lic. No. Jeem - 5
Affiliated to Central Board of Secondary Education
Delhi, India. Affin. No. 5730007 - School No. 90002
E-mail: Info@iisjubail.org
VAT. 310156908100003

المدرسة العالمية الهندية - الجبيل
المنطقة الشرقية - المملكة العربية السعودية
تصريح وزارة التعليم بالمملكة العربية السعودية رقم ج - ٥
بالتعاون مع مجموعة الوسط للتعليم الثانوي
دلهي الهند ،رقم ٥٧٣٠٠٠٧ - مدرسة رقم ٩٠٠٠٢
Website: www.iisjubail.org

IISJ/ADMIN/RFQ_ACC /PUMP_031126/051/2026-27 **Date: 9/11/2026**

Letter of Enquiry
Supply and Installation of 2 Booster Pump Set

We invite competitive **technical and commercial quotations** for the **Supply and Installation of 2 Booster Pump Set** as per the required technical parameters and manufacturer nameplate specifications detailed below:

Sl No	Scope of work	Qty	Unit Rate (SAR)	Amount (SAR)
Supply and Installation of 2 Booster Pump Set (1 Duty+ 1 Stand- By)				
1.	Steel Frame for Pumps			
2.	Maintenance for Sweet Water Pump			
3.	Pressure Tank Bladder			
4.	Labor Charqe for Control Panel			
5.	Change Over			
6.	Contactor			
7.	Automatic Switch			
8.	Check Valve			
9.	Replacement for Second Pump-C15 4 AF(GRUNDFQS/EQUIVALLENT)			
10.	Fire Pump Maintenance			
11.	Pressure Gauge			
12.	Labor Charge for Removing and Installing Pumps with Plumbing Work			



Notes:

1. Supply of new water pump sets as per approved technical specifications.
2. Supply of one complete standby pump set, if required.
3. Dismantling and removal of existing damaged pumps.
4. Installation of new pumps with proper alignment and levelling.
5. Supply and installation of suitable base frames and foundation bolts.
6. Supply and installation of required piping connections.
7. Installation of suitable isolation valves, non-return valves and pressure gauges.
8. Replacement of damaged pipe fittings, flanges, gaskets and flexible connectors, if required.
9. Electrical power cable connection and termination.
10. Connection of the pump to the existing electrical control panel.
11. Checking and adjustment of motor rotation and phase sequence.
12. Testing of suction and discharge pressure.
13. Checking for leakage, vibration, noise and overheating.
14. Testing of automatic operation and standby pump changeover, where applicable.
15. Testing and commissioning of the complete pump system.
16. Removal and disposal of old pump units and installation waste.
17. Final inspection and handover to the client.

INTERNATIONAL INDIAN SCHOOL - AL JUBAIL
Eastern Province - Kingdom of Saudi Arabia
Licenced By Ministry of Education K.S.A. Vide Lic. No. Jeem - 5
Affiliated to Central Board of Secondary Education
Delhi, India. Affin. No. 5730007 - School No. 90002
E-mail: Info@iisjubail.org
VAT. 310156908100003

المدرسة العالمية الهندية - الجبيل
المنطقة الشرقية - المملكة العربية السعودية
تصريح وزارة التعليم بالمملكة العربية السعودية رقم ج - ٥
بالتعاون مع مجموعة الوسط للتعليم الثانوي
دلهي الهند ،رقم ٥٧٣٠٠٠٧ - مدرسة رقم ٩٠٠٠٢
Website: www.iisjubail.org

Important Notice: A site visit is compulsory for all prospective bidders prior to submitting a commercial quote. Bids received from contractors who have not attended the mandatory site visit will be disqualified automatically.

- Site Visit Dates: November 9, 2026, to November 19, 2026.
- **Kindly ensure that the project completion timeline is clearly specified in your quotation, indicating the total number of days required to complete the work.**

Submission Requirements

All bidding suppliers must include the following documentation in their quotation proposal:

1. **Lead Time:** Specify absolute delivery duration to destination site.
2. **Warranty & Support:** Provide details regarding manufacturer standard industrial product warranties.
3. **Data sheets:** Attach dimensional drawings and technical product profile literature to confirm a direct form-fit-function match.
4. **Please attach valid company documents, including Commercial Registration (CR), VAT Certificate, ZATCA Certificate, National Address, and Company Profile.**

Payment Terms

Advance Payment (upon PO issuance): 30%

Balance Payment (upon satisfactory completion & inspection) : 70%

Notes:

1. *Quotation should reach to the Principal office during the office hours (**Sunday to Thursday – from 07:30 am to 02:30 pm, Saturday – From 08:30 am to 11:30 am**) on or before 20/11/ 2026.*
2. *Quotation should be addressed in the name of "Principal - IIS Jubail.*
3. *VAT invoice to be submitted for the payment.*
4. *For more details and any clarification please contact, Tel – 013 362 4130 Ext-242/226 or Email, adminofficer@iisjubail.org or procurementassistant@iisjubail.org.*

Thanks & Regards,

9/11/26

ADMIN OFFICER (INTERIM)
IIS Jubail, KSA

ص. ب ١١٨٨ - الجبيل ٣١٩٥١ - تلفون : ٣٦٢٤١٣٠ / ٣٦٢٣٤١٥ / ٣٦١٧٧٨٣ ١٣ ٩٦٦+ - فاكس : ٣٦١١٠١٨ ١٣ ٩٦٦+
P.O.Box 1188 - Al-Jubail 31951 - Tel: +966 13 3624130 / 3623415 / 3617783 - Fax: +966 13 3611018