



IISJ/ADMIN/RFQ/040/2025-26

Date: 8/2/2026

Letter of Enquiry

SUPPLY AND INSTALLATION OF DATA NETWORKING CABLE

We would like to request you to send us the quotation for **Supply and installation of Data Networking Cable** in our School Main Building for COED LAB (42 System) as per the attached technical specifications.

Please quote the competing price and delivery time for the following.

Sl. No	Item Description	Technical Requirements
01	Patch Cable (1 or 2 Mtr)	Pre-terminated Cat6/Cat6a patch cords for high-speed workstation connectivity.
02	Front Plate	Single Gang White Front Plate for secure and professional I/O termination.
03	Network Module	Tool-less Keystone RJ45 modules; fully compatible with Cat6/Cat6a standards.
04	PVC Box	High-grade surface/concealed back boxes.
05	Installation Services	Full deployment of network cabling, patch paneling hardware mounting, termination of modules, and professional rack dressing.
06	Containment & Connectors	Rigid PVC Trunking and U Curve Trunking for bend-radius protection; includes shielded RJ45 connectors.
07	48-Port Gigabit Switch	Cisco CBS110-48P-4G; 48-Port 10/100/1000 PoE+.
08	Cabinet	6U Wall Mount Rack with front glass door.



## INTERNATIONAL INDIAN SCHOOL - AL JUBAIL

Eastern Province - Kingdom of Saudi Arabia  
Licenced By Ministry of Education K.S.A. Vide Lic. No. Jeem - 5  
Affiliated to Central Board of Secondary Education  
Delhi, India. Affin. No. 5730007 - School No. 90002  
E-mail: Info@iisjubail.org  
VAT. 310156908100003



## المدرسة العالمية الهندية - الجبيل

المنطقة الشرقية - المملكة العربية السعودية  
نصريح وزارة التعليم بالمملكة العربية السعودية رقم ج - ٥  
بالتعاون مع مجموعة الوسط للتعليم الثانوي  
دلهي الهند، رقم ٥٧٣٠٠٠٧ - مدرسة رقم ٩٠٠٠٢  
Website: www.iisjubail.org

### Implementation Standard

**Routing:** All cabling must be routed through specified PVC and Curve Trunking to prevent signal attenuation and maintain structural integrity.

**Testing:** Every node must undergo Fluke testing (or equivalent) for full throughput to ensure zero packet loss during the heavy bandwidth demands of the CBSE notification.

**Labeling:** All I/O points and patch panel ports must be clearly labeled to match the network topology map.

### Notes:

1. Quotation should reach to the principal office during working hours on or before **11<sup>th</sup> February 2026**.
2. Once PO Issued Cabling should be completed within 3 days.
3. School office hours: Sunday to Thursday – from 08:00 am to 01:00 pm  
Saturday – From 08:30 am to 11:30 am.
4. Quotation should be addressed in the name of Principal IIS Jubail.
5. If any clarification, please contact, Tel. 0133624130, 0133623415 – Ext 242/226 /100 or Mob – 0555021095/ 0537380070 Mail @ [procurementassistant@iisjubail.org](mailto:procurementassistant@iisjubail.org) / [adminofficer@iisjubail.org](mailto:adminofficer@iisjubail.org) / [webmaster@iisjubail.org](mailto:webmaster@iisjubail.org)

*Res*  
8/2/26

ADMIN OFFICER(I)  
IIS JUBAIL, KSA

